


NOTES

1. PROVIDE AND INSTALL LOCALLY CERTIFIED SMOKE DETECTORS AS REQUIRED BY NATIONAL FIRE PROTECTION ASSOCIATION (NFFA) AND MEETING THE REQUIREMENTS OF ALL GOVERNING CODES.
2. PROVIDE AND INSTALL GROUND FAULT CIRCUIT INTERRUPTERS (GFI) AS REQUIRED BY NATIONAL ELECTRIC CODE (NEC) AND MEETING THE REQUIREMENTS OF ALL GOVERNING CODES.
3. UNLESS OTHERWISE INDICATED, INSTALL SWITCHES & RECEPTACLES AT THE FOLLOWING HEIGHTS ABOVE FINISH FLOOR:
SWITCHES.....42"
OUTLETS.....16"
TELEPHONE.....16"
TELEVISION.....16"
4. UNLESS OTHERWISE INDICATED, INSTALL VANITY LIGHTS FACE DOWN.
5. MOUNT SMOKE DETECTORS & CO DETECTORS ON WALL IF ATTIC SPACE IS ABOVE CLG. PROVIDE AND INSTALL AS REQUIRED BY NATIONAL ELECTRIC CODE (NEC) AND MEETING THE REQUIREMENTS OF ALL GOVERNING CODES.
6. GARAGE DOOR SCONCE HEIGHTS ON THE SIDES OF THE GARAGE (CENTERED ON THE SPACE AVAILABLE)
7' TALL DOOR: ROUGH IN AT +12" -8' TALL DOOR: ROUGH IN AT +18"
FIXTURES OVER THE GARAGE DOOR - VERIFY WITH BUILDER IN THE FIELD
HEADER SIZES, SOFFITS, FREEZE SPACE AVAILABLE ALL AFFECT WHAT CAN HAPPEN HERE.

ELECTRICAL KEY

- ⊕ DUPLEX CONVENIENCE OUTLET
⊕ DUPLEX OUTLET ABOVE COUNTER
⊕ WEATHERPROOF DUPLEX OUTLET
⊕ QUADPLEX OUTLET
⊕ GROUND FAULT INTERRUPTER DUPLEX OUTLET
⊕ HALF-SWITCHED DUPLEX OUTLET
⊕ SPECIAL PURPOSE OUTLET
⊕ DUPLEX OUTLET IN FLOOR
⊕ 220 VOLT OUTLET
⊕ OUTLET ROUGH-IN
⊕ WALL SWITCH
⊕ THREE-WAY SWITCH
⊕ FOUR-WAY SWITCH
⊕ RHEOSTAT SWITCH
⊕ CEILING MOUNTED INCANDESCENT LIGHT FIXTURE
⊕ WALL MOUNTED INCANDESCENT LIGHT FIXTURE
⊕ RECESSED INCANDESCENT LIGHT FIXTURE
⊕ LIGHT FIXTURE WITH FULL CHAIN
⊕ REINFORCED JUNCTION BOX
⊕ TRACK LIGHT
⊕ FLUORESCENT LIGHT FIXTURE
⊕ EXHAUST FAN
⊕ EXHAUST FAN/LIGHT COMBINATION
⊕ OUTLET FOR GARAGE DOOR OPENER
⊕ CHIMES
⊕ PUSHBUTTON SWITCH
⊕ SMOKE DETECTOR
⊕ TELEPHONE
⊕ TELEVISION
⊕ THERMOSTAT
⊕ ELECTRIC METER
⊕ ELECTRIC PANEL
⊕ DISCONNECT SWITCH
⊕ SPEAKER
⊕ ROUGH-IN FOR CEILING FAN
⊕ CEILING MOUNTED INCANDESCENT LIGHT FIXTURE w/
⊕ ROUGH-IN FOR CEILING FAN
⊕ PENDANT LIGHT
⊕ LED LOW PROFILE FLUSH MOUNT
⊕ CAT6/COAX
⊕ DIMMER SWITCH
⊕ IRRIGATION CONTROL
⊕ LV LOW VOLT TERMINATION



MAIN LEVEL ELECTRICAL PLAN

1/4" = 1'-0"

SLAB ON GRADE



707 COMMERCE DR. #410
WOODBURY, MN 55125
PH. 651-289-6800
FX. 651-501-6600
CREATIVEHOMES.COM

All designs and plans contained in these documents are the original work, owned and property of Creative Homes, Inc. Any reuse or reproduction of these documents in part or whole is strictly prohibited by law without prior written consent from Creative Homes, Inc. Notes and Dimensions are subject to change according to local building codes and site requirements. Consult state and local building regulations and/or Architect/Designer prior to construction related to these documents. Creative Homes, Inc. assumes no liability for changes made to these plans by others.

© Creative Homes, Inc. 2013

JOB INFORMATION

RILEY
2024 BASE PLAN

SQUARE FOOTAGE CALC.			
MAIN LEVEL	1811 SQ FT	1811 SQ FT	
FIN. BASEMENT	N/A SQ FT	N/A SQ FT	
TOTAL FINISHED	1811 SQ FT	1811 SQ FT	
GARAGE	484 SQ FT	484 SQ FT	
FRONT PORCH	54 SQ FT	54 SQ FT	

REVISION LOG:	
ISSUED:	1-27-25
DRAWN BY:	MS
1) CONTRACT SET	INITIALS: X-X-XX
2) REVISION	INITIALS: X-X-XX
3) STRUCT. SIGN OFF	INITIALS: X-X-XX
4) SELECTIONS	INITIALS: X-X-XX
5) INTERNAL AUDIT	INITIALS: X-X-XX
6) INTERNAL PRECON	INITIALS: X-X-XX
7) HFBO	INITIALS: X-X-XX
8) REVISION	INITIALS: X-X-XX
9) REVISION	INITIALS: X-X-XX
10) REVISION	INITIALS: X-X-XX
11) REVISION	INITIALS: X-X-XX
12) REVISION	INITIALS: X-X-XX
13) REVISION	INITIALS: X-X-XX
13) REVISION	INITIALS: X-X-XX
14) REVISION	INITIALS: X-X-XX

PROJECT INFO:	
PLAN NAME:	RILEY
PROJECT NUMBER:	2024-XX
SHEET NUMBER:	6B OF 7